PORTALLY
Port Ailigh

Open Drain:
Install 4m x 300mm Dia
Rigi cross culvert pipe
underneath walkway

New route to be constructed around gorse area. Remove topsoil and place 200mm of capping stone below walkway pavement make up. Due to steep incline, 15m of sleeper steps needed with stone infill.

Ch100

New proposed route to avoid passage through cove

Ch0

Ch200

Proposed New Bridge Crossing with non slip surface - Location to be at the narrowest point at 5m

10m of existing walkway to be widened to 2m and same timber post and rail fencing erected for edge protection -

Ch300

Sand & Shingle

Existing walkway very steep therefore alternative option in blue to be provided

Ch400

Portally Cave

New route to be constructed around gorse area. Remove topsoil and place 200mm of capping stone below walkway pavement make up

Timber Stile

Ch500

PORTALLY
COVE

Oonarontia

Replace existing timber stile

Ch600

Ch700

Erect Agricultural fencing- round timber posts with two strands of high tensile wire.

Ch800

Portally Head

Ch900

Ch1000

Ch1100

Ch1200

Clean inlet and outlet open drain to culvert pipe

Open Drain:
Install 4m x 300mm Dia Rigi cross culvert pipe, stone per detail and level out ditch to form walkway.

Ch1400

Timber Stile

Rathmoylan Cave

Natural Tunnel

Ch1500

Ch1600

Ch1700

Ch1800

Ch1900

Ch2000

Soft Areas:
Remove topsoil and place 200mm of capping stone below walkway pavement make up

Timber Stile

Sand & Shingle

Old Ship's Cave

Old Ship Rocks

Green Cave

Ch1300

Notes:

- Existing Walking Trail - Section 1 (Portally Cove to Ballymacaw Cove)
- Re Routed Walking Trail
- Proposed New Crossing
- Remedial works
- Drainage Issues
- Timber Stile
- Waymarker

Rev.	Date.	Description.	By.	App.

ekce
enda kirwan consulting engineering ltd.
fruithill,
dungarvan,
co. waterford
tel 058 43963
mob 086 2337434
email Info@ekce.ie
web www.ekce.ie

Client:	Waterford City & County Council
Job:	Proposed Portally to Ballymacaw Walking Trail
Drg title:	PART 8 SITE LAYOUT - Sheet 1 of 3

Scale:	Drn:	Job No.	Drg. No.	Rev.
N.T.S.	PS	1903027d	102	1
Date: Sept '19	Chk: EK			