



ekce
 enda kirwan consulting engineering ltd.
 fruthill,
 dungarvan,
 co. waterford
 tel 058 43963
 mob 086 2337434
 email info@ekce.ie
 web www.ekce.ie

Client:	Waterford City & County Council
Job:	Proposed Portally to Ballymacaw Walking Trail
Dwg title:	PART 8 SITE LAYOUT - Sheet 3 of 3
Scale:	N.T.S.
Date:	Sept 19
Dwg. No.:	104
Rev.:	1
Job No.:	1903027D
Dm. PS:	EK

Notes:

- Existing Walking Trail - Section 1 (Portally Cove to Ballymacaw Cove)
- Re Routed Walking Trail
- Proposed New Crossing
- Remedial works
- Drainage Issues
- Timber Stile
- Waymarker



Ballymacaw Bridge:
 Existing walkway line to bridge to be renewed with sleeper steps backfilled with stone to be installed.
 Reservation of bridge handrails Carriglaheen

Existing walkway route to be renewed. Remove topsoil and place 200mm of capping stone below walkway pavement make up.

Widen 5m of existing walkway, extend existing drain with 2m x 300mm Dia Rigi cross culvert pipe and erect timber post and rail fencing for edge protection as same.

Open Drain:
 Install 3m x 400mm Dia Rigi cross culvert pipe, stone per detail and level out ditch to form walkway. Raise levels around existing steps - smoothen and slope to suit

Open Drain:
 Install 5m x 600mm Dia Rigi cross culvert pipe, stone per detail and level out ditch to form walkway.

Erect Agricultural fencing - round timber posts with two strands of high tensile wire

Widening of existing walkway and construct 3ft high dry stone wall on landowner side of same

Proposed main crossing to be of large stepping stones across the stream. Timber sleeper steps to be formed on bank to gain access to cove beach

Existing route to be revised. Remove topsoil and place 200mm of capping stone below walkway pavement make up.

Open Drain:
 Install 4m x 300mm Dia Rigi cross culvert pipe, stone per detail and level out ditch to form walkway.

Erect Agricultural fencing - round timber posts with two strands of high tensile wire